BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/06/2013-14, Date:05.11.2013 **ITEM NO:26**

SCHEDULE-B

NAME OF WORK: Improvements to Roads & Drains in 6th & 7th cross road, at 3rd main road, at Ravindranagara, in Ward no. 13, in SSD

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **SRINIVAS V**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed complete as per specifications.	Cum	224.78	120.02	Rupees One Hundred Twenty and Two Paise Only
2	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	85.2	59.88	Rupees Fifty Nine and Eighty Eight Paise Only
3	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	47.92	4313.84	Rupees Four Thousand Three Hundred Thirteen and Eighty Four Paise Only
4	Removing B.S.Slab of drain and stacking. complete as per specifications.	Sqm	271.58	45.18	Rupees Forty Five and Eighteen Paise Only
5	Refixing Stone slabs of drains and pointing in CM complete as per specifications.	Sqm	271.58	61.74	Rupees Sixty One and Seventy Four Paise Only
6	Providing Granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete as per specifications.	Sqm	40.74	327.08	Rupees Three Hundred Twenty Seven and Eight Paise Only
7	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	284	890.36	Rupees Eight Hundred Ninety and Thirty Six Paise Only

Signature of the Contractor

Executive Engineer

8	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x15x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	284	792.42	Rupees Seven Hundred Ninety Two and Forty Two Paise Only
9	Providing and laying in position plain cement concrete of mix M 15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	14.2	4690.5	Rupees Four Thousand Six Hundred Ninety and Fifty Paise Only
10	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	677.34	1540.0	Rupees One Thousand Five Hundred Forty Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 3 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specifications.	Cum	309.98	70.07	Rupees Seventy and Seven Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,